40B COMPREHENSIVE PERMIT THE VILLAGES AT CRICKET LANE

BYFIELD, MA

DATE: JANUARY 22, 2020

REV: AUGUST 17, 2020

PREPARED FOR:


OWNER/DEVELOPER

CRICKET ROAD DEVELOPMENT, LLC


92 MIDDLESEX ROAD **TYNGSBOROUGH MA, 01879**

INDEX OF DRAWINGS

1 New / New / N		
SHEET	DWG	
NO.	NO.	DRAWING TITLE
	₹ s	
1	CS0001	COVER SHEET
2	CS0002	LEGEND, NOTES AND ABBREVIATIONS
3	CS0201	EXISTING CONDITIONS PLAN (1 OF 2)
4	CS0202	EXISTING CONDITIONS PLAN (2 OF 2)
5	V0801	ROADWAY LAYOUT AND PROPERTY LINE PLAN (1 O
6	V0802	ROADWAY LAYOUT AND PROPERTY LINE PLAN (2 O
7	CS1001	LAYOUT AND MATERIALS PLAN
8	CS1501	GRADING AND DRAINAGE PLAN
9	CS1701	UTILITY PLAN
10	CS3501	ROAD PROFILE
11	CS3502	SEWER PROFILE
12	CS6001	SITE DETAILS
13	CS6021	DRAINAGE DETAILS (1 OF 3)
14	CS6022	DRAINAGE DETAILS (2 OF 3)
15	CS6023	DRAINAGE DETAILS (3 OF 3)
16	CS6031	WETLAND DETAILS
17	CS6051	UTILITY DETAILS
18	CS8001	EROSION AND SEDIMENTATION CONTROL PLAN
19	CS8501	EROSION AND SEDIMENTATION CONTROL NOTES








USGS MAP Scale: N.T.S.



THE LAW REQUIRES NOTIFICATION BY EXCAVATORS, DESIGNERS, OR ANY PERSON PREPARING TO DISTURB THE EARTH'S SURFACE ANYWHERE IN THE STATE AT LEAST 72 HOURS BEFORE BEGINNING CONSTRUCTION. 1-888-DIG-SAFE (1-888-344-7233) WWW.DIGSAFE.COM


PREPARED BY: RANGER ENGINEERING GROUP, INC



Ranger Engineering Group, Inc.

13 Branch Street, Suite 101 Methuen, MA 01844 Tel: 978-208-1762

NOT FOR CONSTRUCTION





		всо	900	ВУ
		REVIEW COMMENT REVISIONS	REVIEW COMMENT REVISIONS	REVISIONS
		2	-	NO.
		08/17/2020	06/26/2020	DATE

AS NOTED

CS0001

a. THE LOCUS IS SHOWN ON TOWN OF NEWBURY ASSESSOR'S MAP R-20 LOT 75, LOCATED IN ZONING DISTRICT

b. TOPOGRAPHY SHOWN ON THIS PLAN IS A RESULT OF A FIELD SURVEY PERFORMED BY TTI ENVIRONMENTAL, INC. DURING

d. WETLANDS DELINEATION BY RIMMER ENVIRONMENTAL INC. IN DECEMBER 2015 AND UPDATED IN OCTOBER AND NOVEMBER 2017

e. TEST PITS PERFORMED BY TTI ENVIRONMENTAL IN NOVEMBER 2015 AND BY RANGER ENGINEERING AND DESIGN, LLC IN

a. PLAN BOOK 152, PLAN 63, "DEFINITIVE PLAN, HIGHFIELDS NEWBURY, MASSACHUSETTS, PREPARED BY PORT ENGINEERING

b. PILAN BOOK 396, PLAN 5, "APPROVAL NOT REQUIRED PLAN, PIKE DEVELOPMENT LLC, ORCHARD STREET NEWBURY, MASSACHUSETTS, PREPARED BY CAMMETT ENGINEERING, DATED:11-06-05, SCALE: 1*=40'.

THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY AND HAVE NOT BEEN

THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK AND AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY THE CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES. THE CONTRACTOR IS TO CONTACT "DIG SAFE" AT

ALL CURBING ON SITE SHALL BE SLOPED GRANITE CURB (SGC) WITH A 6 INCH VERTICAL REVEAL UNLESS OTHERWISE NOTED.

GRAVEL BASE COURSE: 6 INCHES SELECT COMPACTED DENSE GRADES CRUSHED STONE FOR SUBBASE (M2.01.7)

ALL DISTURBED AREAS NOT COVERED BY STRUCTURES OR PAVEMENT AND NOT OTHERWISE SPECIFIED ON THE LANDSCAPE PLAN SHALL RECEIVE 6 INCHES OF TOPSOIL (M1.07.0). THESE AREAS ARE TO BE SEEDED AND WATERED UNTIL A HEALTHY STAND OF

AREAS OUTSIDE THE LIMITS OF PROPOSED WORK DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED BY THE

LAYOUT DIMENSIONS ARE FROM FACE OF BUILDINGS, RETAINING WALLS, CURBS OR BERMS.

ALL SITTE SIGNAGE AND PAVEMENT MARKINGS SHALL CONFORM TO THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES.

ALL HANDICAPPED ACCESSIBLE RAMPS AND SIDEWALKS SHALL BE CONSTRUCTED IN CONFORMANCE WITH THE AMERICANS WITH DISABIILITIES ACT AND THE MASSACHUSETTS ARCHITECTURAL ACCESS BOARD (WHICHEVER IS MORE RESTRICTIVE).

THE LOCATION AND ELEVATIONS OF EXISTING UTILITIES AS SHOWN ON THESE PLANS ARE BASED ON THE SURVEY NOTED ABOVE AND SHALL BE VERIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION AND PRIOR TO ORDERING STRUCTURES.

THE LOCATION, SIZE, DEPTH, AND SPECIFICATIONS FOR CONSTRUCTION OF PROPOSED PRIVATE UTILITY SERVICES SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS PROVIDED BY, AND APPROVED BY, THE RESPECTIVE UTILITY COMPANY (GAS, TELEPHONE OR ELECTRIC). FINAL DESIGN AND LOCATIONS AT THE BUILDING WILL BE PROVIDED BY THE ARCHITECT. THE CONTRACTOR SHALL COORDINATE THE INSTALLATION OF THE UTILITY CONNECTIONS WITH THE RESPECTIVE UTILITY COMPANIES PRIOR TO ANY UTILITY

STORM DRAIN PIPING SHALL BE HIGH DENSITY POLYETHYLENE PIPE (HDPE) WITH CORRUGATED EXTERIOR, SMOOTH LINED WITH

RIM ELEVATIONS OF PROPOSED DRAINAGE MANHOLES AND ASSOCIATED STRUCTURES ARE APPROXIMATE. FINAL ELEVATIONS. ARE TO BE SET FLUSH AND CONSISTENT WITH THE GRADING PLAN. ADJUST ALL OTHER RIM ELEVATIONS OF MANHOLES, WATER GATES,

a. THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES AND, WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD, THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUST CALL THE APPROPRIATE UTILITY COMPANY AT LEAST 72 HOURS BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATION OF UTILITIES. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELOCATE ALL EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THE PLANS.

b. ALL NECESSARY INSPECTIONS AND/OR CERTIFICATION REQUIRED BY CODES AND/OR UTILITY SERVICE COMPANIES SHALL BE PERFORMED PRIOR TO ANNOUNCED BUILDING POSSESSION AND THE FINAL CONNECTION OF SERVICES.

LEGEND: PROPOSED LEGEND: EXISTING A HYDRANT

- - -	חוטתאמוו	BUILDING	
SMH ()	SEWER MANHOLE		(11111111111111111111111111111111111111
DWH	DRAIN MANHOLE		
EMH ()	ELECTRIC MANHOLE	BIT. CONC. PAVEMENT	
тмн 🔾	TELEPHONE MANHOLE		
MH ()	MANHOLE (UNKNOWN TYPE)	BIT. CONC. SIDEWALK	
св 🏢	CATCH BASIN	BIT. CONC. DRIVEWAY	
•	AREA DRAIN	Bitt GONG. BittVEW/()	
	METAL COVER	SPOT ELEVATION	46.34 x
<u></u>	LIGHT POLE	LIGHT	\$
		LIGHT	*
G	GAS METER	SIGN	-0-
M	VALVE	CONTOUR	600
WG ⊛	WATER GATE		The state of the s
∽ ø	UTILITY POLE	WATER LINE DOMESTIC	
STL	STEAM LINE	SANITARY SEWER	000 17% i i demokrati producti in i producti i producti p
UGE	UNDERGROUND ELECTRIC LINE	STORM SEWER	
S	SEWER LINE	GAS LINE	UGUGUG
D	DRAIN LINE	UNDERGROUND ELECTRIC	
W	WATER LINE	OVERHEAD ELECTRIC	
DS	DOMESTIC WATER SERVICE	FOUNDATION DRAIN	
— FP ———	FIRE PROTECTION SERVICE		
G	GAS LINE	ROOF DRAIN	D
- C	UNDERGROUND CABLE	SANITARY MANHOLE	S
T	TELEPHONE LINE	CTODEA DO AINI EAANU IOU C	
— OH——	OVERHEAD WIRES	STORM DRAIN MANHOLE	0
~~~~~	TREE LINE	STORM DRAIN INLET	
39	EXISTING CONTOURS	STORM DRAIN FLARED END SECTION	<
40	EXISTING CONTOUR (5' INTERVAL)		~
< 100.00	EXISTING SPOT GRADE	CONIFEROUS TREE	
-XXX	CHAIN LINK FENCE WOOD FENCE	DECIDUOUS TREE	(\cdot)
• ⊕	BOLLARD		
CONC.	CONCRETE	TREE LINE	.~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~
BIT. CONC.	BITUMINOUS CONCRETE		
/GC	VERTICAL GRANITE CURBING	FIRE HYDRANT	.
CLF	CHAIN LINK FENCE	WATER VALVE	
3CB	BITUMINOUS CONCRETE BERM		
	SIGN	CONSTRUCTION ENTRANCE	0202020
\odot	TREE	CH T CACK	
<u>L</u>	FLAG POLE	SILT SACK	
AC	AIR CONDITIONER UNIT	SILT FENCE/SILT SOCK	SF manufacture SF manufacture manufacture SF manufacture manufactu
RIM=	RIM ELEVATION	SILT FENCE/SILT SOCK	HDSF
EL.	ELEVATION	WETLAND FLAG	a s seeme see s
INV	INVERT	WE LEARN PLAG	Committee and an advantage of the committee of the commit

PROP. WETLAND REPLACEMENT


RCP REINFORCED CONCRETE PIPE

TEST PIT

SOIL BORING

SOIL BORING WITH MONITORING WELL

POLYVINYL CHLORIDE PIPE




rangereng.com


Ranger Engineering Group, Inc. 13 Branch Street, Suite 101 Methuen MA, 01844 Tel: 978-208-1762

		BCO	всо	BY	
		REVIEW COMMENT REVISIONS	REVIEW COMMENT REVISIONS	REVISIONS	
		2	- Quino	NO.	
		08/17/2020	06/26/2020	DATE	

15-1516 2020-08-10 DRAWING SCALE AS NOTED DRAWN BY OMR APPROVED BY

SHEET 2 OF 19





 ELEVATION
 AREA

 53.5
 4,355 SF ±

 54.0
 14,810 SF ±

 54.3
 19,115 SF ±

 ADDITIONAL AREA

 EXTENDING OFF-SITE

1,495 SF ± AT A DEPTH OF 12 INCHES ±

TOTAL VOLUME = 0.26 ACRE FT

VOLUME CALCULATIONS:

'A' SERIES CALCULATIONS


VOLUME ELEV. 53.5 TO 54.0 = 4,355 + 14,810 / 2 X .5 = 4,791 CUBIC FT


VOLUME ELEV. 54.0 TO 54.3 = 14,810 + 19,115 / 2 X .3 = 5,089 CUBIC FT

VOLUME EXTENDING OFF-SITE = 1,495 X 1 = 1,495 CUBIC FT

TOTAL = 11,375 CUBIC FT

ACRE FT = CUBIC FT / 43,560 = 0.26





Ranger Engineering Group, Inc.
13 Branch Street, Suite 101
Methuen MA, 01844
Tel: 978-208-1762

rangereng.com



BYFIELD (NEWBURY), MA 01922
ASSESSOR'S MAP R-20 LOT 75

EXISTING CONDITIONS PLAN

 08/17/2020
 2
 REVIEW COMMENT REVISIONS
 BCO

 06/26/2020
 1
 REVIEW COMMENT REVISIONS
 BCO

 DATE
 NO.
 REVISIONS
 BY

PROJECT 15-1516


DATE 2020-08-10


DRAWING SCALE AS NOTED


DRAWN BY OMR

CS0202

SHEET 4 OF 19








Ranger Engineering Group, Inc.
13 Branch Street, Suite 101
Methuen MA, 01844
Tel: 978-208-1762 rangereng.com







2020-08-10 AS NOTED DRAWING SCALE DRAWN BY OMR APPROVED BY

V0802

SHEET 6 OF 19






Ranger Engineering Group, Inc. 13 Branch Street, Suite 101 Methuen MA, 01844 Tel: 978-208-1762




15-1516 2020-08-10 DRAWING SCALE AS NOTED OMR

CS1001


SHEET 7 OF 19








Ranger Engineering Group, Inc. 13 Branch Street, Suite 101 Methuen MA, 01844 Tel: 978-208-1762



15-1516 2020-08-10 AS NOTED

APPROVED BY



Ranger Engineering Group, Inc.
13 Branch Street, Suite 101
Methuen MA, 01844
Tel: 978-208-1762
rangereng.com



AGE AT CRICKET LANE
SYFIELD (NEWBURY), MA 01922
ASSESSOR'S MAP R-20 LOT 75
ROAD PROFILE

06/26/2020 1 REVIEW COMMENT REVISIONS BY BY BY

PROJECT 15-1516


DATE 2020-08-10


DRAWING SCALE AS NOTED

DRAWN BY OMR

APPROVED BY BCC

SHEET 10 OF 19





Ranger Engineering Group, Inc.

Ranger Engineering Group, Inc.
13 Branch Street, Suite 101
Methuen MA, 01844
Tel: 978-208-1762
rangereng.com



2

ASSESSOR'S MAP R-20 LOT 75

SITE DETAILS


CRICKET ROAD DEVELOPMENT, LLO

2020 2 REVIEW COMMENT REVISIONS BCO
2020 1 REVIEW COMMENT REVISIONS BCO
E NO. REVISIONS BY

15-1516 2020-08-10 CALE AS NOTED


APPROVED BY BC

SHEET 12 OF 19




Ranger Engineering Group, Inc 13 Branch Street, Suite 101

Methuen MA, 01844 Tel: 978-208-1762 rangereng.com



15-1516 2020-08-10 AS NOTED DRAWING SCALE

APPROVED BY CS6021




Ranger Engineering Group, Inc. 13 Branch Street, Suite 101 Methuen MA, 01844




15-1516 2020-08-10 AS NOTED

CS6022




Ranger Engineering Group, Inc 13 Branch Street, Suite 101 Methuen MA, 01844



15-1516 2020-08-10 AS NOTED

SHEET 15 OF 19



Tel: 978-208-1762

rangereng.com

Ranger Engineering Group, Inc.
13 Branch Street, Suite 101
Methuen MA, 01844

BENJAMIN C.
OSGOOD JR.
CIVIE
No. 45891

ROGISTERE

WETLAND DETAILS

8/17/2020 2 REVIEW COMMENT REVISIONS BCO
6/26/2020 1 REVIEW COMMENT REVISIONS BCO
DATE NO. REVISIONS BY

 ROJECT
 15-1516


 ATE
 2020-08-10

 RAWING SCALE
 AS NOTED


 RAWN BY
 OMR


CS6031


SHEET 16 OF 10



- 1. WHERE UTILITY TRENCHES ARE CONSTRUCTED THROUGH DETENTION BASIN BERMS OR OTHER SUCH SPECIAL SECTIONS, PLACE TRENCH BACKFILL WITH MATERIALS SIMILAR TO THE SPECIAL SECTION REQUIREMENTS.
- 2. USE METALLIC TRACING/WARNING TAPE OWER ALL PIPES.











92000-00000000000-00-00-00-00-00-00-00-00					**************************************				
TABLE OF DIMEN	NOISI	S							
TEES	G	Н	I	J	TEES G H I J				
6"x 6"x 6"	12"	24"	24"	18"	12"x 12"x 6" 12" 24" 24" 18	3"			
8"x 8"x 6"	"	æ	11	11	12"x 12"x 8" " " 24	4"			
8"x 8"x 8"	39	HY.	11	24"	12"x 12"x 12" " 36" " 36	H			
<u>TEES</u>									
2 UNDISTURBED									
			Ţ						
	PL/	<u>AN</u>		SO	SECTION 2-2				

- 1. PROVIDE BLOCKS FOR TAPPING SLEEVES, DEAD ENDS, GATE VALVES, AND VERTICAL BENDS (SAME SIZE AS REQUIRED FOR TEES). PROVIDE ANCHOR RODS AT VERTICAL BENDS AND GATE
- 2. CONCRETE SHALL NOT BE PLACED AGAINST PIPE BEYOND FITTING.
- 3. CONCRETE SHALL BE 3000 PSI-TYPE |.









Ranger Engineering Group, Inc. 13 Branch Street, Suite 101 Methuen MA, 01844 Tel: 978-208-1762 rangereng.com




 $\overline{\Box}$


15-1516 2020-08-10 DRAWING SCALE AS NOTED DRAWN BY OMR BCO

CS6051

SHEET 17 OF 19

NOT FOR CONSTRUCTION





Ranger Engineering Group, Inc. 13 Branch Street, Suite 101 Methuen MA, 01844



15-1516 2020-08-10 AS NOTED OMR

BCO

SHEET 18 OF 19

EROSION CONTROL NOTES (DURING CONSTRUCTION)

- 1. THE CONTRACTOR MUST INSTALL EROSION CONTROL MEASURES AS SHOWN ON THE PLANS AND IN THE DETAILS PRIOR TO STARTING ANY OTHER WORK ON THE SITE. EROSION CONTROL MUST BE INSTALLED AT EVERY INLET STRUCTURE (EXISTING AND PROPOSED) AND MAINTAINED FOR THE DURATION OF THE
- 2. THE CONTRACTOR SHALL CHECK THE CONDITION OF EROSION CONTROLS DAILY TO KEEP THEM IN GOOD OPERATING CONDITION. EROSION CONTROLS SHALL ALSO BE INSPECTED, REPAIRED AND MAINTAINED BY THE CONTRACTOR WITHIN 112 HOURS OF ANY STORM EVENT PRODUCING 1/2 INCH OF RAINFALL OR MORE EROSION CONTROLS SHALL BE REPLACED WHEN DETERIORATED, OR WHEN ORDERED BY THE ENGINEER. SEDIMENT DEPOSITS SHALL BE REMOVED WHEN THEY REACH A DEPTH OF 6 INCHES.
- 3. SEDIMENT DEPOSITS SHA! L BE REMOVED WHEN THEY REACH A DEPTH OF 6 INCHES.
- 4. SEDIMENT SHALL BE CONTAINED WITHIN THE CONSTRUCTION SITE, AWAY FROM DRAINAGE STRUCTURES.
- 5. STABILIZE SLOPES STEEPER THAN 3:1 (HORIZONTAL TO VERTICAL) WITH SEED, SECURED GEOTEXTILE FABRIC, OR ROCK RIP-RAP AS REQUIRED TO PREVENT EROSION DURING CONSTRUCTION.
- 6. CLEAN OUT ALL CATCH BASINS, DRAIN MANHOLES, AND STORM DRAIN PIPES AFTIER COMPLETION OF CONSTRUCTION,
- 7. LOAM AND SEED ALL DISTURBED AREAS.
- 8. UPON ESTABLISHMENT OF PERMANENT VEGETATION OVER DISTURBED AREAS, REMOVE AND DISPOSE OF HAYBALES, STAKES, AND SILT FENCE.
- 9. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO MAINTAIN AND SUPPLEMENT THE SPECIFIED SEDIMENTATION CONTROLS AS NECESSARY TO PREVENT SEDIMENTATION OF OFF-SITE AREAS AND/OR ANY REGULATED RESOURCE AREAS. FAILURE BY THE CONTRACTOR TO CONTROL EROSION, POLLUTION, AND/OR SILTATION SHALL BE CAUSE FOR THE OWNER TO EMPLOY OUTSIDE ASSISTANCE OR TO USE HIS OWN MEANS TO PROVIDE THE NECESSARY CORRECTIVE MEASURE. THE COST OF SUCH ASSISTANCE PLUS PROJECT ENGINEERING COSTS WILL BE THE CONTRACTOR'S RESPONSIBILITY.
- 10. IN ADDITION TO THOSE LOCATIONS SHOWN ON THIS PLAN AND ON THE GRADING AND DRAINAGE PLANS, EROSION CONTROLS SHALL BE INSTALLED AT THE FOLLOWING LOCATIONS: TOE OF SLOPE OF EMBANKMENT CONSTRUCTION, TOE OF TEMPORARY EARTHWORK STOCKPILES.
- 11. EROSION AND SEDIMENTATION CONTROL SHALL BE IN COMPLIANCE WITH MASSACHUSETTS STORMWATER POLICY.

CONSTRUCTION SEQUENCE NOTES:

- 1. INSTALL EROSION AND SEDIMENT CONTROLS AS SHOWN ON PLAN
- COMMENCE CLEARING, GRUBBING, AND EARTHWORK.
- 3. PERFORM EARTHWORK OPERATIONS. ALL CUT AND FILL SLOPES SHALL BE SEEDED AND MULCHED WITHIN 72 HOURS AFTER BEING CONSTRUCTED. TEMPORARY GRADED AREAS SHOULD BE STABILIZED WITH MULCH BY OCTOBER 1ST, SO AS NOT TO BE LEFT EXPOSED DURING WINTER CONDITIONS.
- 4. INSTALL SITE DRAINAGE AND UTILITIES.
- 5. STABILIZE SIDE SLOPES. SIDE SLOPES MUST BE FULLY STABILIZED BEFORE ANY STORMWATER DISCHARGE
- 6. INSTALLATION OF UNDERGROUND UTILITIES AND CATCH BASINS SHALL BE PROTECTED FROM SEDIMENT IN ACCORDANCE WITH THE PLANS. THE CONTROLS SHALL REMAIN UNTIL THE SITE IS SUFFICIENTLY STABILIZED. ALL PERMANENT STORMWATER MANAGEMENT MEASURES SHALL HAVE A HEALTHY STAND OF VEGETATION ESTABLISHED PRIOR TO DIRECTING RUNOFF INITO THEM.
- 7. AS THE BUILDING(S) ARE COMPLETED, ALL DISTURBED AREAS SHALL BE PERMANIENTLY STABILIZED WITHIN 72 HOURS.
- FINAL PAVING OF ROADWAY AND DRIVEWAYS.
- 9. INSPECT ALL SEDIMENT AND EROSION CONTROL MEASURES.
- 10. AFTER ALL SEEDED AREAS HAVE ESTABLISHED STABLE GROWTH, ALL TEMPORARY EROSION CONTROL CAN BE REMOVED.
- 11. CONTRACTOR SHALL NOTIFY AND COORDINATE WITH ALL AUTHORITIES RESPONSIBLE FOR INSPECTIONS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO OBTAIN ALL REQUIRED INSPECTION SIGN-OFFS.

FOR A MORE COMPLETE DESCRIPTION OF CONSTRUCTION PHASING AND EROSION CONTROL SEE PROJECT STORMWATER REPORT AND SWPPP.

OPERATION AND MAINTENANCE:

CONSTRUCTION PHASE

THE BMPS ASSOCIATED WITH THIS PROJECT WILL BE OWNED BY THE PROJECT DEVIELOPER, WHO WILL BE RESPONSIBLE FOR INSPECTION, OPERATION AND MAINTENANCE DURING THE CONSTRUCTION PHASE.


- 1. THE CONTRACTOR IS TO INSTALL AND MAINTAIN DRAINAGE FACILITIES AS SHOWIN ON PLAN (BY RANGER ENGINEERING GROUP, INC).
- 2. PRIOR TO CONSTRUCTION, ALL EROSION/SILTATION CONTROL DEVICES SHOWN ON ABOVE PLAN ARE TO BE INSTALLED. TO PREVENT SILT INTRUSION INTO THE DRAINAGE SYSTEM DURING CONSTRUCTION, THE CONTRACTOR IS TO INSTALL AND MAINTAIN INLET PROTECTION AT ALL CATCH BASINS, AND SET A SILT FENCE AND HAY BALES AT ALL SLOPES WHICH MAY ERODE IN THE DIRECTION OF ANY OPEN DRAINAGE FACILITIES. SUCH PREVENTIVE MEASURES ARE TO BE MAINTAINED THROUGHOUT THE CONSTRUCTION PROCESS.
- 3. ALL CONSTRUCTION OF DRAINAGE FACILITIES IS TO BE INSPECTED BY RANGER ENGINEERING GROUP, INC. TO VERIFY CONFORMANCE TO THE DESIGN
- 4. THE SEQUENCE OF DRAINAGE CONSTRUCTION SHALL BE AS FOLLOWS:
- A. CLEAR, GRUB, EXCAVATE AREAS FOR DRAINAGE SYSTEMS. B. TRENCH AND INSTALL PIPES, CATCH BASINS MANHOLES
- C. INSTALL INLET PROTECTION.
- 5. EROSION CONTROLS ARE TO BE INSPECTED AND MAINTAINED ON A WEEKLY BASIS. UPON DISCOVERY OF SILT BUILD-UP IN ANY CATCH BASIN SUMPS, OR ANY OTHER STRUCTURES, THEY ARE TO BE CLEANED.
- 6. ALL EXPOSED SOILS SHALL BE IMMEDIATELY STABILIZED WITH A LAYER OF MULCH HAY OR JUTE BLANKETS-AS NEEDED FOR SLOPES STEEPER THAN
- 7. UPON INSTALLATION OF CATCH BASINS, INLET PROTECTION-AS DESCRIBED ON SITE PLANS- SHALL BE INSTALLED AND MAINTAINED UNTIL READY FOR PAVING.
- 8. PRIOR TO CONSTRUCTION OF IMPERVIOUS AREAS, ALL DRAINAGE STRUCTURES AND PIPES SHALL BE INSTALLED AND INSPECTED FOR PROPER FUNCTION. DURING CONSTRUCTION OF OTHER SITE FEATURES, ALL DRAINAGE FACILITIES SHALL BE INSPECTED ON A WEEKLY BASIS AND CLEANED/REPAIRED IMMEDIATELY UPON DISCOVERY OF SEDIMENT BUILD-UP OR DAMAGE
- 9. AFTER PAVING IS INSTALLED, IT SHALL BE SWEPT CLEAN ON A REGULAR BASIS.
- 10. THE ENTIRE DRAINAGE SYSTEM MUST BE VACUUMED OUT BEFORE THE ISSUANCE OF THE LAST CERTIFICATE OF OCCUPANCY.


POST-DEVELOPMENT PHASE


THE OWNER/OCCUPANT IS TO BE RESPONSIBLE FOR MAINTENANCE OF ALL DRAINAGE STRUCTURES IN THE PROJECT - INCLUDING ROOF DRAINS, AND DRAIN PIPES. THE FUTURE OWNER IS EXPECTED TO BE THE PROJECT ASSOCIATION, WHO WILL ULTIMATELY BE RESPONSIBLE FOR COMPLIANCE WITH THE PLAN. IN THE EVENT OF CHANGE OF OWNERSHIP, THE O & M PLAN SHALL BE TRANSFIERRED TO THE NEW OWNER.


REGULAR MAINTENANCE IS TO INCLUDE THE FOLLOWING:

- 1. INSPECTION OF ALL DRAINAGE FACILITIES (CATCH BASINS, PIPES AND DETENTION BASINS, EVERY THREE MONTHS, DURING THESE INSPECTIONS, THE INSPECTOR (A REGISTERED PROFESSIONAL CIVIL ENGINEER QUALIFIED IN DRAININGE SYSTEMS AS DESIGNATED BY THE PROJECT ASSOCIATION) SHALL LOOK FOR EVIDENCE OF THE FOLLOWING: STRUCTURAL DAMAGE, SILT ACCUMULATION (NEAR INLET INVERTS ON CATCH BASINS, INFILTRATORS), AND IMPROPER FUNCTION. A REPORT ON THE SYSTEM SHALL BE DELIVERED TO THE PROJECT ASSOCIATION, WITH A COPY DELIVERED TO THE TOWN ENGINEER.
- 2. AFTER INSPECTION, IF ANY OF THE ABOVE CONDITIONS EXIST, THE INSPECTOR SHALL NOTIFY THE PROJECT ASSOCIATION. WHO SHALL IMMEDIATELY ARRANGE FOR ALL NECESSARY REPAIRS AND/OR SEDIMENT REMOVAL.
- 3. THE ROAD WAY IS TO BE SWEPT CLEAN, AS REQUIRED (I.E., VISUALLY NOTICEABLE DEBRIS BUILD-UP). A MINIMUM OF ONCE PER YEAR.
- 4. ALL GRADED SLOPES SHALL BE INSPECTED EVERY SPRING FOR EROSION. UPON DISCOVERY OF ANY FAILURE (IE. EROSION), LOAM AND SEED SHALL BE PUT IN PLACE AND NURTURED.
- 5. ALL SNOW IS TO BE STORED IN THE DESIGNATED SNOW STORAGE AREAS AS DEPICTED ON SHEET 7 CS1001.










NOTES:

TEMPORARY CHECK DAM DETAIL

- 1. ENTRANCE WIDTH SHALL BE A TWENTY-FIVE (25) FOOT MINIMUM, BUT NOT LESS THAN THE FULL WIDTH AT POINTS WHERE INGRESS OR EGRESS OCCURS.
- 2. THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH SHALL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHTS-OF-WAY MUST BE REMOVED IMMEDIATELY. BERM SHALL BE PERMITTED. PERIODIC INSPECTION AND MAINTENANCE SHALL BE PROVIDED AS NEEDED.





SECTION VIEW


NOTES:


1. INSTALL SILTSACK IN ALL CATCH BASINS WHERE INDICATED ON THE PLANE BEFORE COMMENCING WORK OR IN PAVED AREAS AFTER BINDER COURSE ID PLACED AND HAY BALES HAVE BEEN REMOVED.

EXPANSION RESTRAINT

- 2. GRATE TO BE PLACED OVER SILTSACK.
- 3. SILTSACK SHALL BE INSPECTED WEEKLY AND AFTER ALL STORM EVENTS AND CLEANING OR REPLACEMENT SHALL BE PERFORMED PROMPTLY AS NEEDED. MAINTAIN UNTIL UPSTREAM AREAS HAVE BEEN PERMANENTLY STABILIZED.
- 4. SILTSACKS SHALL NOT BE INSTALLED WITHIN PARK ST. DURING THE WINTER MONTHS.








1. ENCLOSE STRUCTURE WITH HAYBALES IMMEDIATELY AFTER CATCH BASIN CONSTRUCTION. MAINTAIN WINTIL PAVING BINDER COURSE IS COMPLETE OR A PERMANENT STAND OF GRASS HAS BEEN ESTABLISHED.

Section View

- 2. IF GRATE IS AGAINST EXISTING CURB THEM HAY BALES ARE TO BE PLACED AROUND THREE SIDES OF GRATTE ONLY.
- GRATE TO BE PLACED OVER FILTER FABRIC.
- 4. BALES SHALL BE INSPECTED PERIODICALLY AND AFTER ALL STORM EVENTS. REPAIR OR REPLACEMENT SHALL BE PERFORMED PROMPTLY AS NEEDED.



NOT FOR CONSTRUCTION



Ranger Engineering Group, Inc. Methuen MA, 01844 Tel: 978-208-1762 rangereng.com



FABRIC W/4"x 4"

OPENINGS. FASTEN TO

15-1516 2020-08-10 DRAWING SCALE AS NOTED DRAWN BY OMR

BCO

APPROVED BY